

Application guide

Henry® LowSlope™ One-Ply Roof-In-A-Roll

Tools: Utility knife with hook blade, hammer, caulking gun, chalk line, trowel, seam roller (optional) or paint roller for deck primer application, measuring tape

Acceptable deck materials: Minimum 15/32" (12 mm) plywood or oriented strand board (OSB). Plank or mill decks are not acceptable. Decks must be well secured without excessive defection. Nails and screws must be secure to prevent backout. Loose fasteners should be removed.

Fasteners: Minimum 3/4" (19 mm) nails through 1" (25 mm) metal caps, sufficient to penetrate deck


Deck primer: Use Henry® 545 Aquatac™ Primer

Rubberized sealant: Use Henry® 900 Construction and Flashing Sealant, Henry® Polybitume® 570-05 or Henry® 925 BES

Sealant

Available warranty: 15 years (see packaging for details)

1. Preparation




Install metal drip edge at rake and eave. Apply primer by roller or pump-up sprayer at a rate of approx. 300 ft²/gal. (28 m²/3.78 L). Allow to dry.

2. Sheet installation



Cut rolls in half and allow to lay flat to relax for 20 minutes. Align at eave.

3. Sheet installation



Tack nails in place along selvedge, sufficient to hold sheet temporarily. Do not drive fully as they will later be removed.

4. Sheet installation



Fold back lower portion of sheet and apply rubberized sealant to metal edge and rake.

5. Sheet installation



Remove release film from lower portion and set in place. Be careful to ensure that sheet lays flat and wrinkle free.

6. Sheet installation



Remove nails. Apply sealant to rake; release film from the upper portion and adhere in place.

7. Sheet installation



Install subsequent rows by removing the release film as well as the zip strip, then adhering the upper portion.

8. Sheet installation




Seal at rake and set in place. Apply pressure at laps (image 14).

9. End laps




Overlap 6" (150 mm).

10. End laps



And mark. Stagger end laps.

11. End laps




Apply rubberized sealant prior to adhering in place. Miter corner of second or middle sheet at "T" joints.

12. End laps




Spread sealant over granulated area to be overlapped.

13. End laps




Remove release film and set in place.

14. End laps



Ensure a proper seal especially at edges and overlaps by applying foot pressure...

15. End laps




... or by using a roller.

16. Wall flashing



Remove lower two boards from wall to provide even substrate. Extend sheet up wall 8" (200 mm) and nail at top 12" (300 mm) apart on center.

17. Wall flashing



Set chalk line 6" (150 mm) out from wall.

18. Wall flashing



Apply sealant over granules.

19. Wall flashing




Spread sealant over surface evenly with trowel. Allow to dry for 1 hour minimum.

20. Wall flashing




Cut flashing membrane to size. Set in sealant and nail at top 12" (300 mm) apart on center. Re-install siding after completion to cover top of flashing.

21. Ridge detail



Extend ply sheets to ridge. Snap chalk line 6" (150 mm) on each side of ridge.

22. Ridge detail



Apply sealant along chalked line. Cut strips of sheet and set into sealant. Note: Roof slope not shown to scale.

23. Ridge detail




Nail through 3" (76 mm) selvedge.

24. Ridge detail




Continue installing ridge flashing sheets overlapping 3" (76 mm) and nailing through 3" (76 mm) selvedge.

25. Ridge alternative



Run ply sheet "A" over ridge 6' (150 mm). Run ply sheet from other side of roof "B" over ridge a minimum of 6" (150 mm). Set in sealant where sheet overlaps granules.


29. Skylights and curbs



Turn ply sheets up at curb a minimum of 2" (50 mm) and nail 8" (200 mm) apart on center.


33. Valley

26. Vent (soil pipe)




Stop application of sheet at soil pipe. Place pre-formed flashing over soil pipe.


30. Skylights and curbs




Install flashing sheet, beginning at the low end, extending 6" (150 mm) out from curb. Set in sealant. Nail at top of curb 8" (200 mm) apart on center.



34. Chimney flashing




Plan detail




-flashing sheets

27. Vent (soil pipe)




1. Cut piece 4" (100 mm) larger than flashing. 2. Set in sealant spread 3" (76 mm) wide around perimeter. 3. Apply sealant over granulated flashing at lap line and around pipe.

31. Skylights and curbs



Complete flashing sheets on all sides, setting in sealant. Set skylight in place or provide metal



cap flashing.


Continue application.

28. Vent (soil pipe)




Run final ply sheet a minimum 18" (454 mm) under shingles. Set lower portion of final ply sheet into sealant as shown by shaded area.

35. Chimney flashing



Run ply sheets a minimum of 2" (50 mm) up chimney.


36. Chimney flashing



Trowel apply sealant 8" (200 mm) up chimney and 6" (150 mm) on to the roof surface. Allow to set for minimum of 1 hour.


37. Chimney flashing

Center sheet in valley. Do not install shingle nails within 12" (300 mm) of centerline of valley.




Install flashing sheet "A". Extend 8" (200 mm) up chimney and 6" (150 mm) on to roof surface.

38. Chimney flashing



Install flashing sheets "B", "C" and "D". Install termination bar at top of flashing sheet and apply bead of sealant.

39. Chimney flashing



Henry and Polybitume are trademarks of the Henry Company



Building Envelope Systems®Roofing | Air Barrier | Waterproofing

Ask us today about other Henry® solutions that help manage the flow of water, air, vapor and energy.